Nile Gate Solutions S.A.E.
41 Corniche Road, Maadi, Cairo · Branch office: Al-Noor Business Park, Tower B · tenders@nilegate.example

ENVELOPE 1 · TECHNICAL PROPOSAL

Supply, Installation, Commissioning and Maintenance of High-Energy Cargo X-Ray Inspection Systems

Port of Al-Noor · Tender NGPA/T/2026/014

SAMPLE · FICTIONAL

Submitted to	Northern Gulf Ports Authority, Tender Committee Secretariat
Bidder	**Nile Gate Solutions S.A.E.** (Egypt)
Our reference	NGS/2026/T-014-T
Date	9 December 2026
Contact	Mona Fahmy, Tender Manager · tenders@nilegate.example · +20 2 0000 0000

SAMPLE DOCUMENT. This bid and the company that submits it are fictional. The document was created to test procurement-evaluation software and is not a real offer.

Nile Gate Solutions S.A.E.
41 Corniche Road, Maadi, Cairo · Branch office: Al-Noor Business Park, Tower B · tenders@nilegate.example

Form F-1 — Bid submission letter (technical)

NGS/2026/T-014-T · 9 December 2026

To: The Chair, Tender Committee, Northern Gulf Ports Authority

We, Nile Gate Solutions S.A.E., acting as the authorised partner of **Corvanta Imaging Ltd.** (the OEM) for this tender, submit our technical proposal for tender NGPA/T/2026/014. We acknowledge receipt of **Addendum No. 1** of 28 October 2026 and have taken it into account.

The tender-specific OEM authorisation (Form F-3) signed by Corvanta Imaging is enclosed. This technical envelope contains no prices. The bid is valid for 120 days from 14 December 2026. Where our offer differs from the requirements, the differences are stated openly in Form F-2 and Form F-6.

For and on behalf of Nile Gate Solutions S.A.E.
Hesham Abdelrahman, Chief Executive Officer

Date: 9 December 2026
Company seal

Contents

1. Company, OEM partner and experience
2. Offered systems
3. Imaging and operations
4. Radiation safety, site fit and power
5. Environmental conditions and power continuity
6. VisionCore software and the CIAC
7. Integration and OCR
8. Cybersecurity
9. Workstations and user interface
10. Implementation and acceptance
11. Training
12. Warranty, support and maintenance
Annex 1. Form F-2 — Technical compliance matrix
Annex 2. Form F-6 — Statement of deviations (technical)

SAMPLE · FICTIONAL

1. Company, OEM partner and experience

Nile Gate Solutions is a systems integrator specialised in customs and port security technology. Founded in 2006 in Cairo, the company has operated a branch office in the State since 2014, with 64 permanent staff in-country, including engineers, civil works supervisors and Arabic-speaking trainers. Nile Gate has delivered 14 cargo inspection projects as Corvanta's partner in the region, and has integrated inspection systems with national customs risk engines and single-window platforms.

Corvanta Imaging Ltd. manufactures the CX series of high-energy inspection systems and supplies the linear accelerators, detectors and VisionCore software. Corvanta guarantees the supply of spare parts for 10 years after PAC and supports Nile Gate with second-level engineering.

Form F-4 — References (Corvanta systems delivered by Nile Gate)

Site	Scope	Year	Climate
Port of Mirsal, Bulk & General Cargo Terminal	2 × CX-45 DE drive-through, local analysis room	2020	Mean summer max 42 °C, RH 78 %
Red Valley land port	3 × CX-45 DE, integration with the national risk engine	2022	Mean summer max 44 °C, RH 25 %
Port of Sela, Container Terminal 1	2 × CX-45 DE + relocatable CX-45 R	2024	Mean summer max 34 °C, RH 70 %

2. Offered systems

Four Corvanta CX-series systems with a **4.5 MeV dual-energy** linear accelerator:

Site	Model	Views	Steel penetration	Throughput
T1 Gate A	CX-45 DE	Top + side	290 mm	160 trucks/h
T1 Gate B	CX-45 DE	Top + side	290 mm	160 trucks/h
T2 main gate	CX-45 DE	Top + side	290 mm	160 trucks/h
Relocatable	CX-45 R	Top	290 mm	160 trucks/h

The 4.5 MeV source keeps the controlled area and the shielding compact, which matters especially on the 70 m × 28 m T2 plot, and lowers the electrical demand of each system.

3. Imaging and operations

Parameter	Value	Verification
Steel penetration (ANSI N42.46-2008)	290 mm, all sites	FAT + SAT
Wire detection behind 100 mm steel	1.0 mm Cu	FAT
Contrast sensitivity	1.0 %	FAT
Material discrimination	4 classes	FAT

SAMPLE — FICTIONAL

Throughput, driver in cab	160 trucks/h	SAT, 4-hour test
Scan speed	5–12 km/h	SAT
Tunnel	4.6 m × 3.0 m	Drawing
MTTR, line-replaceable units	≤ 3 hours	Maintenance records

4. Radiation safety, site fit and power

The beam starts only after the driver cab has passed the beam plane (cab detection by laser scanner and loop, redundant). No cab scan is offered. The calculated annual dose at the controlled-area boundary is 0.8 mSv at full throughput. Emergency stops, interlocks, beam-on lights, audible alarms and Arabic/English signs are provided.

Site	Plot	Controlled area	Demand incl. HVAC	Available
T1 Gate A / B	95 × 36 m	76 × 26 m	185 kVA	400 kVA
T2 main gate	70 × 28 m	64 × 25 m	185 kVA	250 kVA
Relocatable, T1 pad	80 × 32 m	62 × 26 m	110 kVA	160 kVA
Relocatable, T2 pad	60 × 30 m	56 × 26 m	110 kVA	100 kVA + 150 kVA generator (Nile Gate supply)

Radiation Licensing Support Plan (Addendum No. 1, A4)

Our licensed radiation protection officer, resident in the State, prepares each system's licence file (shielding report, radiation protection programme, emergency plan) in Arabic and English for submission by the Employer: T1 Gate A in month 1, the other systems in month 3. Nile Gate coordinates the regulator's inspections before each SAT and supplies personal dosimeters for operators for the first 12 months.

5. Environmental conditions and power continuity

Continuous operating ambient temperature **0 °C to +45 °C** (Corvanta type-test), humidity up to 95 % non-condensing, outdoor enclosures IP54, C5-M coating system, wind survival 120 km/h. Operator cabins are air-conditioned with N+1 units. Supply 400 V ±10 %, 3-phase, 50 Hz. UPS: 60 minutes for control systems and servers, 30 minutes for workstations.

6. VisionCore software and the CIAC

Corvanta VisionCore is installed entirely on-premise at the CDC and the terminals. The licence is activated once with an offline licence file; no telemetry, licence check or update service connects outside the Employer's network. Updates are delivered on signed media and installed by our engineers with the Employer's administrators.

Storage: 1,170,000 scans × 45 MB × 5 years = 263.25 TB, plus 20 % headroom = 315.9 TB. We offer **330 TB usable** (RAID 6 + hot spares). Images and metadata are kept online for 5 years and can be exported in DICOS

SAMPLE · FICTIONAL

format. Workload routing between the CIAC and terminal analysts keeps the expected 90th-percentile decision time within 3 minutes. VisionCore Assist offers automated anomaly highlighting for undeclared goods, weapons, cigarettes and currency, running on the CDC servers only.

7. Integration and OCR

Nile Gate's integration team has connected inspection systems to three national customs risk engines. CRMS: bidirectional REST/JSON (requests, results, image links, annotations). TOS: UN/EDIFACT COPARN/CODECO or REST. OCR: container numbers per ISO 6346 with check digit (98.5 %) and Arabic/Latin licence plates (98.2 %). All middleware included.

8. Cybersecurity

AD over LDAPS with RBAC; MFA for administrators; 5-year tamper-evident audit logs forwarded to the Employer's SIEM (syslog); AES-256 at rest and TLS 1.2+ in transit; SBOM and quarterly patches during warranty and CMC; independent penetration test before go-live with critical and high findings closed; vendor remote access only through the Employer's VPN, per session and recorded.

9. Workstations and user interface

20 workstations (10 CIAC, 5 T1, 3 T2, 2 spare/mobile) per Addendum No. 1. Each workstation has **two 27-inch monitors at 1920 × 1080**, colour-calibrated, 32 GB RAM and a dedicated GPU. The VisionCore interface is fully bilingual (Arabic/English) and shows Gregorian and Hijri dates.

10. Implementation and acceptance

Milestone	Month
Surveys, design approval, licence files	M1–M2
Civil works (Nile Gate's own civil team)	M1–M5
FAT at Corvanta factory (4 Employer witnesses, travel at our cost)	M3
T1 Gate A in trial operation	M5
All systems SAT, integration and penetration test	M6–M7
PAC of all systems	M8

Our local presence allows parallel civil works on all sites from month 1, which is why we can offer PAC one month ahead of the RFP's 9-month limit.

11. Training

All courses are delivered in Arabic by Nile Gate's own certified trainers: operators (40 participants, 5 days, on site), analysts (12 participants, 10 days at the CIAC plus 20 days on-the-job coaching), maintenance engineers (6 participants, 15 days at the Corvanta factory, with an Arabic-speaking Nile Gate engineer) and system

administrators (2 participants, 5 days at the CDC). A train-the-trainer programme is included. Documentation in Arabic and English.

12. Warranty, support and maintenance

Warranty: 24 months starting from the date of shipment from the factory, covering spare parts and labour. The X-ray source (linear accelerator) is a consumable and is excluded from the warranty; replacement sources are supplied at Corvanta list price.

Support: our existing service centre in the State has **three Corvanta-certified engineers** and holds critical spare parts in-country. On-site response at T1/T2 within 8 hours, remote response within 2 hours, 24/7. Guaranteed availability of 98 % per scanner per month. Spare parts available for 10 years after PAC.

CMC: five years after warranty, covering preventive and corrective maintenance, spare parts (except the X-ray source) and VisionCore updates.

SAMPLE · FICTIONAL

Annex 1. Form F-2 — Technical compliance matrix

One row per Annex B requirement, as amended by Addendum No. 1. "Reference" points to the section of this proposal.

Ref	Requirement	Status	Offered	Reference
TB-01	Steel penetration (ANSI N42.46): T1 A/B ≥ 310 mm, T2 ≥ 300 mm, relocatable ≥ 280 mm	Partially comply	290 mm at all sites	§2–3
TB-02	Wire detection behind 100 mm steel ≤ 1.0 mm Cu	Comply	1.0 mm Cu	§3
TB-03	Dual-energy X-ray source	Comply	4.5 MeV dual-energy	§2
TB-04	Contrast sensitivity ≤ 1.0 %	Comply	1.0 %	§3
TB-05	Material discrimination ≥ 4 classes	Comply	4 classes	§3
TB-06	Dual-view (top + side) imaging (optional for relocatable)	Comply	Top + side (fixed); top (relocatable)	§2
TB-07	Throughput, driver in cab: T1 Gate A ≥ 180/h; T1 Gate B, T2 ≥ 150/h; relocatable ≥ 120/h (A5)	Partially comply	160 trucks/h at all sites	§3
TB-08	Vehicle speed during scan 5–15 km/h	Comply	5–12 km/h	§3
TB-09	Inspection tunnel ≥ 4.6 m × 3.0 m (H × W)	Comply	4.6 × 3.0 m	§3
TB-10	High-energy beam never on occupied driver cab	Comply	Redundant cab detection	§4
TB-11	Driver dose per pass ≤ 0.25 µSv (if cab scan offered)	Comply	No cab scan offered	§4
TB-12	Annual dose at controlled-area boundary ≤ 1 mSv	Comply	0.8 mSv/yr	§4
TB-13	Controlled area + exclusion zones fit the site plots	Comply	T2: 64 × 25 m	§4
TB-14	Emergency stops, interlocks, beam-on lights, audible alarms	Comply	Provided	§4
TB-15	Continuous operating ambient 0 … +50 °C	Partially comply	0 … +45 °C	§5
TB-16	Relative humidity ≤ 95 % non-condensing	Comply	≤ 95 %	§5
TB-17	Outdoor electronics enclosures ≥ IP54	Comply	IP54	§5
TB-18	Steel coating C5-M (ISO 12944)	Comply	C5-M	§5
TB-19	Wind survival 120 km/h	Comply	120 km/h	§5
TB-20	Supply 400 V ±10 %, 3-phase, 50 Hz	Comply	400 V, 3-ph, 50 Hz	§5

TB-21	Maximum demand per system ≤ site capacity	Comply	185 kVA; 110 kVA + generator at T2 pad	§4
TB-22	UPS autonomy, control systems and servers ≥ 60 min (A3)	Comply	60 min	§5
TB-23	UPS autonomy, workstations ≥ 30 min	Comply	30 min	§5
TB-24	On-premise hosting of all components incl. licensing, telemetry, updates	Comply	All on-premise, offline licence	§6
TB-25	Data residency: in-country only	Comply	In-country	§6
TB-26	Online retention of images and metadata: 5 years	Comply	5 years	§6
TB-27	Usable storage at CDC per RFP §4.6.3 (state usable TB)	Comply	330 TB usable	§6
TB-28	DICOS (NEMA IIC 1) export	Comply	DICOS export	§6
TB-29	CRMS bidirectional REST/JSON integration	Comply	REST/JSON	§7
TB-30	TOS integration: EDIFACT COPARN/CODECO or REST	Comply	EDIFACT or REST	§7
TB-31	OCR container numbers (ISO 6346) ≥ 98 %	Comply	98.5 %	§7
TB-32	OCR licence plates, Arabic + Latin ≥ 98 %	Comply	98.2 %	§7
TB-33	Scan-to-analyst-decision time, 90th percentile ≤ 3 min	Comply	≤ 3 min expected	§6
TB-34	AD via LDAPS, RBAC, MFA for administrators	Comply	LDAPS, RBAC, MFA	§8
TB-35	Tamper-evident audit log retention 5 years	Comply	5 years	§8
TB-36	Encryption AES-256 at rest / TLS ≥ 1.2 in transit	Comply	AES-256 / TLS 1.2+	§8
TB-37	Vendor remote access via Employer VPN, per session, recorded	Comply	Employer VPN	§8
TB-38	Operator/analyst UI in Arabic and English	Comply	Arabic + English	§9
TB-39	Hijri + Gregorian date display	Comply	Gregorian + Hijri	§9
TB-40	Monitors: 2 × 27", ≥ 2560 × 1440 per workstation	Partially comply	2 × 27" at 1920 × 1080	§9
TB-41	Workstations: 20 in total (A2)	Comply	20	§9
TB-42	Relocation T1 ↔ T2 incl. re-commissioning ≤ 72 h	Comply	72 hours	§2
TB-43	Availability per scanner per month ≥ 98 %	Comply	98 %	§12
TB-44	On-site response 24/7 ≤ 24 h	Comply	8 hours	§12
TB-45	Spare parts availability ≥ 10 years after PAC	Comply	10 years	§12

Annex 2. Form F-6 — Statement of deviations (technical)

RFP reference	Deviation	Explanation
RFP §4.1.1 / TB-01	Steel penetration 290 mm at all sites.	The 4.5 MeV source gives a compact controlled area and lower power demand; 290 mm covers the large majority of declared cargo densities at the port.
RFP §4.2.1 / TB-07	Throughput 160 trucks/h at T1 Gate A.	Meets the 150 trucks/h requirement at all other lanes.
RFP §4.4.1 / TB-15	Operating ambient temperature up to +45 °C.	Operator cabins and electronics cabinets are air-conditioned with N+1 redundancy.
RFP §4.10.1 / TB-40	Monitors 1920 × 1080.	Full-HD monitors at 27 inches are used by all our current customers' analysts.
RFP §6.1.1	Warranty period starts on shipment from the factory.	Corvanta's standard warranty terms.
RFP §6.1.2	X-ray source excluded from warranty (consumable).	Corvanta's standard warranty terms; sources are supplied at list price.
RFP §6.3.2	Three OEM-certified engineers at the local service centre.	Our existing centre with three certified engineers has served all our regional installations; additional engineers come from Cairo within 24 hours.

For and on behalf of Nile Gate Solutions S.A.E.
Hesham Abdelrahman, Chief Executive Officer

Date: 9 December 2026
Company seal

SAMPLE FICTIONAL