Atlas Port Technologies Ltd.
27 Makariou Avenue, 3030 Limassol, Cyprus · bids@atlasport.example

ENVELOPE 1 · TECHNICAL PROPOSAL

Supply, Installation, Commissioning and Maintenance of High-Energy Cargo X-Ray Inspection Systems

Port of Al-Noor · Tender NGPA/T/2026/014

SAMPLE · FICTIONAL

Submitted to	Northern Gulf Ports Authority, Tender Committee Secretariat
Bidder	**Atlas Port Technologies Ltd.** (Cyprus)
Our reference	APT/NGPA/014-T
Date	2 December 2026
Contact	Karim Haddad, Bid Manager · bids@atlasport.example · +357 25 000 000

SAMPLE DOCUMENT. This bid and the company that submits it are fictional. The document was created to test procurement-evaluation software and is not a real offer.

Atlas Port Technologies Ltd.
27 Makariou Avenue, 3030 Limassol, Cyprus · bids@atlasport.example

Form F-1 — Bid submission letter (technical)

APT/NGPA/014-T · 2 December 2026

To: The Chair, Tender Committee, Northern Gulf Ports Authority

Atlas Port Technologies submits the enclosed technical proposal for the supply and installation of high-energy cargo X-ray inspection systems at the Port of Al-Noor, tender NGPA/T/2026/014. We acknowledge receipt of Addendum No. 1.

Atlas designs and manufactures the Sentinel 6D systems offered. No prices are included in this technical proposal.

For and on behalf of Atlas Port Technologies Ltd.
Karim Haddad, Bid Manager

Date: 2 December 2026
Company seal

Contents

1. Company and references
2. Sentinel 6D inspection systems
3. Image quality
4. Safety and site layout
5. Environment and power
6. Atlas Vision software
7. Integration
8. Cybersecurity
9. Workstations
10. Schedule
11. Training
Annex 1. Form F-2 — Technical compliance matrix
Annex 2. Form F-6 — Statement of deviations (technical)

SAMPLE · FICTIONAL

1. Company and references

Atlas Port Technologies was founded in 2009 by engineers from the cargo-inspection industry. The company designs and assembles the Sentinel range of high-energy and mobile X-ray systems in Limassol, with 140 employees. Atlas focuses on high image quality and rugged design for hot climates.

Site	Scope	Year	Climate
Port of Ras Tamar, Container Terminal	2 × Sentinel 6D drive-through	2021	Mean summer max 43 °C, RH 74 %
Eastern Highway border post	1 × Sentinel 6D	2023	Mean summer max 39 °C, RH 30 %
Port of Velar, Ro-Ro terminal	1 × Sentinel 6D + 1 × Sentinel 6R	2025	Mean summer max 33 °C, RH 75 %

2. Sentinel 6D inspection systems

Atlas offers three Sentinel 6D drive-through systems (T1 Gate A, T1 Gate B, T2) and one Sentinel 6R relocatable system. All use a **6 MeV dual-energy** linear accelerator.

Site	Model	Views	Penetration	Throughput
T1 Gate A	Sentinel 6D	Top + side	320 mm	up to 165 trucks/h
T1 Gate B	Sentinel 6D	Top + side	320 mm	up to 165 trucks/h
T2 main gate	Sentinel 6D	Top + side	320 mm	up to 165 trucks/h
Relocatable	Sentinel 6R	Top + side	300 mm	up to 140 trucks/h

3. Image quality

Atlas image chains use cadmium-tungstate detectors with 16-bit acquisition, giving a contrast sensitivity of **0.9 %**, wire detection of 1.0 mm Cu behind 100 mm of steel and discrimination of 5 material classes. The tunnel measures 4.8 m × 3.2 m and accepts 45' high-cube containers. Scan speed 5–12 km/h.

4. Safety and site layout

The primary beam is started by the cab-detection system only after the cab has passed; no cab scanning is offered. Boundary dose below 1 mSv per year. Emergency stops and interlocks on all doors and the lane, beam-on lights and sirens, signage in Arabic and English.

Site	Plot	Controlled area	Demand
T1 Gate A / B	95 × 36 m	88 × 32 m	220 kVA
T2 main gate	70 × 28 m	70 × 28 m	220 kVA
Relocatable	80 × 32 m / 60 × 30 m	72 × 30 m / 58 × 29 m	150 kVA

SAMPLE FICTIONAL

5. Environment and power

Operating range 0 °C to +52 °C, humidity up to 95 %, IP55 enclosures, C5-M coating system, wind survival 140 km/h. Power supply 400 V three-phase 50 Hz. UPS autonomy of 30 minutes for control systems, servers and workstations at full load, as required by RFP §4.5.2.

6. Atlas Vision software

Atlas Vision is installed on servers at the Customs Data Center and the terminals, licensed with an offline licence file; it does not require any internet connection. Storage: 1,170,000 scans × 45 MB × 5 years = 263 TB; with 20 % headroom 316 TB; we offer **320 TB usable**. Five-year online retention, DICOS export, workload routing between the CIAC and the terminals (expected decision time about 3 minutes). Optional AI module "Atlas Detect" for weapons and cigarettes.

7. Integration

REST/JSON interface to the CRMS; EDIFACT COPARN/CODECO interface to the TOS; OCR of container numbers (ISO 6346, check digit) and Arabic/Latin licence plates with ≥ 98 % read rates.

8. Cybersecurity

Active Directory over LDAPS, role-based access, MFA for administrators, audit logs kept 5 years, AES-256 encryption at rest and TLS 1.2 in transit, remote access only through the Employer's VPN with session recording. Penetration testing before go-live.

9. Workstations

24 workstations as per RFP §3.3.1 (12 CIAC, 6 T1, 4 T2, 2 spare), each with two 27-inch 2560 × 1440 monitors, 32 GB RAM and a dedicated GPU. Arabic and English user interface.

10. Schedule

Activity	Month
Design and site surveys	M1–M2
Manufacturing and FAT in Limassol	M2–M5
Civil works	M3–M6
T1 Gate A installation and start of trial operation	M7
Other systems and CIAC	M7–M8
PAC	M9

SAMPLE · FICTIONAL

11. Training

Operator training for 40 participants (5 days, on site) and analyst training for 12 participants (10 days at the CIAC) in English with Arabic interpretation. Maintenance training for 6 engineers is delivered at our regional training centre (5 days).

SAMPLE · FICTIONAL

Annex 1. Form F-2 — Technical compliance matrix

One row per Annex B requirement, as amended by Addendum No. 1. "Reference" points to the section of this proposal.

Ref	Requirement	Status	Offered	Reference
TB-01	Steel penetration (ANSI N42.46): T1 A/B ≥ 310 mm, T2 ≥ 300 mm, relocatable ≥ 280 mm	Comply	320 mm; 300 mm relocatable	§2
TB-02	Wire detection behind 100 mm steel ≤ 1.0 mm Cu	Comply	1.0 mm Cu	§3
TB-03	Dual-energy X-ray source	Comply	6 MeV dual-energy	§2
TB-04	Contrast sensitivity ≤ 1.0 %	Comply	0.9 %	§3
TB-05	Material discrimination ≥ 4 classes	Comply	5 classes	§3
TB-06	Dual-view (top + side) imaging (optional for relocatable)	Comply	Top + side, all systems	§2
TB-07	Throughput, driver in cab: T1 Gate A ≥ 180/h; others ≥ 150/h	Comply	Up to 165 trucks/h	§2
TB-08	Vehicle speed during scan 5–15 km/h	Comply	5–12 km/h	§3
TB-09	Inspection tunnel ≥ 4.6 m × 3.0 m (H × W)	Comply	4.8 × 3.2 m	§3
TB-10	High-energy beam never on occupied driver cab	Comply	Cab detection	§4
TB-11	Driver dose per pass ≤ 0.25 µSv (if cab scan offered)	Comply	No cab scan	§4
TB-12	Annual dose at controlled-area boundary ≤ 1 mSv	Comply	< 1 mSv	§4
TB-13	Controlled area + exclusion zones fit the site plots	Comply	See layout table	§4
TB-14	Emergency stops, interlocks, beam-on lights, audible alarms	Comply	Yes	§4
TB-15	Continuous operating ambient 0 … +50 °C	Comply	0 … +52 °C	§5
TB-16	Relative humidity ≤ 95 % non-condensing	Comply	95 %	§5
TB-17	Outdoor electronics enclosures ≥ IP54	Comply	IP55	§5
TB-18	Steel coating C5-M (ISO 12944)	Comply	C5-M	§5
TB-19	Wind survival 120 km/h	Comply	140 km/h	§5
TB-20	Supply 400 V ±10 %, 3-phase, 50 Hz	Comply	400 V 3-ph 50 Hz	§5
TB-21	Maximum demand per system ≤ site capacity	Comply	220 / 150 kVA	§4

TB-22	UPS autonomy, control systems and servers ≥ 30 min	**Comply**	30 min	§5
TB-23	UPS autonomy, workstations ≥ 30 min	**Comply**	30 min	§5
TB-24	On-premise hosting of all components incl. licensing, telemetry, updates	**Comply**	On-premise, offline licence	§6
TB-25	Data residency: in-country only	**Comply**	Yes	§6
TB-26	Online retention of images and metadata: 5 years	**Comply**	5 years	§6
TB-27	Usable storage at CDC per RFP §4.6.3 (state usable TB)	**Comply**	320 TB	§6
TB-28	DICOS (NEMA IIC 1) export	**Comply**	Yes	§6
TB-29	CRMS bidirectional REST/JSON integration	**Comply**	REST/JSON	§7
TB-30	TOS integration: EDIFACT COPARN/CODECO or REST	**Comply**	EDIFACT	§7
TB-31	OCR container numbers (ISO 6346) ≥ 98 %	**Comply**	≥ 98 %	§7
TB-32	OCR licence plates, Arabic + Latin ≥ 98 %	**Comply**	≥ 98 %	§7
TB-33	Scan-to-analyst-decision time, 90th percentile ≤ 3 min	**Comply**	About 3 min	§6
TB-34	AD via LDAPS, RBAC, MFA for administrators	**Comply**	Yes	§8
TB-35	Tamper-evident audit log retention 5 years	**Comply**	5 years	§8
TB-36	Encryption AES-256 at rest / TLS ≥ 1.2 in transit	**Comply**	AES-256 / TLS 1.2	§8
TB-37	Vendor remote access via Employer VPN, per session, recorded	**Comply**	Employer VPN	§8
TB-38	Operator/analyst UI in Arabic and English	**Comply**	Arabic + English	§9
TB-39	Hijri + Gregorian date display			
TB-40	Monitors: 2 × 27", ≥ 2560 × 1440 per workstation			
TB-41	Workstations: 24 in total			
TB-42	Relocation T1 ↔ T2 incl. re-commissioning ≤ 72 h			
TB-43	Availability per scanner per month ≥ 98 %			
TB-44	On-site response 24/7 ≤ 24 h			
TB-45	Spare parts availability ≥ 10 years after PAC			

SAMPLE

Annex 2. Form F-6 — Statement of deviations (technical)

The Bidder declares that this proposal contains **no deviations** from the tender documents, including Addendum No. 1.

For and on behalf of Atlas Port Technologies Ltd.
Karim Haddad, Bid Manager

Date: 2 December 2026
Company seal

SAMPLE · FICTIONAL