NORTHERN GULF PORTS AUTHORITY · HEALTH, SAFETY & ENVIRONMENT DIRECTORATE

REQUEST FOR PROPOSAL · NGPA/T/2026/052

Air Quality and Noise Monitoring Network

Port of Al-Noor and the neighbouring district of Al-Sahil

SAMPLE · FICTIONAL

Tender reference	**NGPA/T/2026/052**
Procedure	Open tender · two envelopes (technical / commercial)
Date of issue	12 October 2026
Bid closing date	10 December 2026, 12:00 local time
Contact	Tenders Office · tenders@ngpa.example

SAMPLE DOCUMENT. This tender, the issuing authority and the sites are fictional. The document was created to demonstrate procurement-evaluation software.

Requirements marked **MANDATORY** are mandatory: a bid that does not meet them may be rejected. **IMPORTANT** and **DESIRABLE** requirements are scored.

1. Background

1.1 The Port of Al-Noor borders the residential district of Al-Sahil. The port's environmental permit, renewed in 2026, requires continuous monitoring of air quality and noise at the port boundary and in Al-Sahil, with monthly and annual reports to the Environment Agency.

1.2 The Northern Gulf Ports Authority (the Authority) seeks a monitoring network, its data platform and three years of operation and maintenance. Today the port relies on two portable samplers and quarterly noise surveys.

2. Scope

2.1 Six fixed air-quality stations (sites AQ-1 to AQ-6: four at the port boundary, two in Al-Sahil) measuring PM10, PM2.5, NO2, SO2 and O3, each with meteorological sensors for wind speed and direction, temperature and humidity. **MANDATORY**

2.2 Four permanent noise monitoring terminals (sites N-1 to N-4). **MANDATORY**

2.3 A data platform for data collection, validation, alarms, reports and a public dashboard. **MANDATORY**

2.4 Three years of operation and maintenance after acceptance, including calibration, consumables, repairs and data validation. **MANDATORY**

3. Station requirements

3.1 PM10 and PM2.5 analysers shall be certified as equivalent to the EN reference method (EN 16450) by an accredited body. Certificates shall be attached to the bid. **MANDATORY**

3.2 NO2 shall be measured by chemiluminescence (EN 14211), SO2 by UV fluorescence (EN 14212) and O3 by UV photometry (EN 14625). **MANDATORY**

3.3 Noise terminals shall be Class 1 to IEC 61672-1, with an all-weather microphone kit, 1/3-octave spectra and audio recording of exceedances. **MANDATORY**

3.4 Each station shall be housed in an air-conditioned shelter rated IP55 or better, for ambient temperatures from 0 °C to +50 °C, with a UPS of at least 2 hours. **IMPORTANT**

3.5 Stations shall store at least 7 days of data locally and resend it automatically after an outage. Communication over 4G with a backup link (second operator or fixed line). **IMPORTANT**

3.6 Data capture of at least 90 % valid hourly data for every pollutant in every calendar quarter. **IMPORTANT**

4. Data platform

4.1 The platform and all monitoring data shall be hosted on the Authority's servers in its data centre. Raw and validated data shall be kept for 10 years. **MANDATORY**

4.2 Automatic validation (range, rate of change, flat-line checks) and manual validation, with an audit trail of every change. **IMPORTANT**

SAMPLE · FICTIONAL

4.3 Alarms for limit-value exceedances to the HSE duty officer by SMS and e-mail within 5 minutes of the end of the averaging period. IMPORTANT

4.4 Monthly and annual reports in the format of the environmental permit, exported to Excel and PDF. IMPORTANT

4.5 A public dashboard in Arabic and English and an open, documented REST API for the published data. DESIRABLE

4.6 Users sign in with their accounts in the Authority's Active Directory. IMPORTANT

5. Implementation and services

5.1 All stations and terminals shall be in operation within 6 months of contract signature, followed by a 30-day trial run before acceptance. IMPORTANT

5.2 Analysers shall be calibrated at least every 3 months with gases traceable to a laboratory accredited to ISO/IEC 17025. Calibration records shall be kept for 5 years. MANDATORY

5.3 On-site response within 48 hours to a station failure, with spare analysers kept in the State. IMPORTANT

5.4 Warranty of 24 months from acceptance on all equipment and software, and 3 years of operation and maintenance. MANDATORY

5.5 Training of 6 HSE staff in station operation and data validation, in Arabic and English. DESIRABLE

6. Qualification

6.1 The bidder shall have installed at least 3 similar monitoring networks (4 or more stations each) in the last 7 years, with client contacts. MANDATORY

6.2 The bidder shall have an office or an authorised service partner in the State. IMPORTANT

7. Commercial conditions

7.1 Prices in USD, excluding VAT. Operation and maintenance shall be priced per year, and these prices shall be fixed for the 3 years. IMPORTANT

7.2 Payments follow delivery and acceptance milestones. Any advance payment shall not exceed 20 % and requires an advance-payment guarantee. IMPORTANT

7.3 Performance security of 10 % of the contract price, issued by a bank licensed in the State. MANDATORY

7.4 Bid validity of 120 days. Bid security of USD 25,000, issued by a bank licensed in the State. MANDATORY

8. Evaluation

8.1 Mandatory requirements are pass/fail. Compliant bids are scored 70 % technical (measurement quality 30, data platform 20, operation and maintenance 30, references 20) and 30 % financial.

8.2 Evaluated price = supply and installation + 3 years of operation and maintenance.

8.3 Bidders shall complete the compliance matrix in Annex 1.

SAMPLE — FICTIONAL

Chair, Tender Committee
Northern Gulf Ports Authority

Issued: 12 October 2026
Reference: NGPA/T/2026/052

SAMPLE · FICTIONAL

Annex 1. Compliance matrix (to be completed by the bidder)

For each clause, state Comply, Partially comply or Do not comply, and the section of the technical proposal where the requirement is answered.

Clause	Requirement	Response	Reference in the proposal
2.1	Six AQ stations: PM10, PM2.5, NO2, SO2, O3 + meteorology		
2.2	Four noise terminals		
3.1	PM analysers certified equivalent (EN 16450)		
3.2	Gas analysers to EN reference methods		
3.3	Noise Class 1, 1/3-octave, audio recording of exceedances		
3.4	Shelter IP55, 0 to +50 °C, UPS ≥ 2 h		
3.5	7 days local storage, back-fill, backup link		
3.6	≥ 90 % valid hourly data per quarter		
4.1	Authority data centre; 10-year retention		
4.2	Validation with audit trail		
4.3	Alarms within 5 min (SMS, e-mail)		
4.4	Monthly / annual permit reports (Excel, PDF)		
4.5	Public dashboard AR/EN + REST API		
4.6	Active Directory sign-in		
5.1	In operation ≤ 6 months; 30-day trial		
5.2	Calibration every 3 months, ISO/IEC 17025 traceable		
5.3	48 h on-site response; spares in the State		
5.4	24-month warranty; 3-year O&M		
5.5	Training of 6 HSE staff, AR/EN		
6.1	≥ 3 similar networks in 7 years		
6.2	Office or service partner in the State		

SAMPLE — fictional tender created for a software demonstration. Not a real procurement.