NORTHERN GULF PORTS AUTHORITY · TERMINAL MODERNISATION PROGRAMME

REQUEST FOR PROPOSAL · NGPA/T/2026/031

Smart Gate Automation System for the Terminal 2 Truck Gates

Port of Al-Noor · Container Terminal 2

SAMPLE · FICTIONAL

Tender reference	**NGPA/T/2026/031**
Procedure	Open tender · two envelopes (technical / commercial)
Date of issue	5 October 2026
Bid closing date	30 November 2026, 12:00 local time
Contact	Tender Committee Secretariat · tenders@ngpa.example

SAMPLE DOCUMENT. This tender, the issuing authority and the sites are fictional. The document was created to demonstrate procurement-evaluation software.

Requirements marked **MANDATORY** are mandatory: a bid that does not meet them may be rejected. **IMPORTANT** and **DESIRABLE** requirements are scored.

1. Background

1.1 Container Terminal 2 handles about 2,800 truck visits per day through 4 in-gate lanes and 2 out-gate lanes. Gate clerks check container numbers, seals, truck plates and documents by hand; a transaction takes 4 minutes on average and at peak hours queues reach the port access road.

1.2 The Northern Gulf Ports Authority (the Authority) seeks a Smart Gate Automation System that identifies trucks and containers automatically, checks every visit against the truck appointment and the customs release, and opens the barrier without clerk intervention when everything is in order.

2. Scope of supply

2.1 OCR portals for all 6 lanes, reading container numbers and ISO type codes, truck licence plates and seal presence, and taking damage-inspection images of every container.

2.2 UHF RFID readers on every lane and 3,000 windscreen RFID tags for the registered haulier fleet.

2.3 A self-service kiosk on every lane, with a touchscreen, an intercom to the gate control room and a gate-pass printer.

2.4 A Gate Operating System (GOS) for lane control, exception handling and reporting, with workstations for 4 clerks in the gate control room.

2.5 Integration with the Terminal 2 Terminal Operating System (TOS), the Vehicle Booking System of the Port Community System (PCS) and the customs release status.

2.6 Design, supply, civil works for the portal foundations, installation, testing, training, a 24-month warranty and 3 years of maintenance after the warranty.

3. Technical requirements

3.1 The OCR shall read container numbers (with ISO 6346 check-digit validation) with an accuracy of at least 98 %, and truck plates with Arabic and Latin characters with an accuracy of at least 97 %, by day and night, at truck speeds up to 15 km/h. **MANDATORY**

3.2 Damage-inspection images of the four sides and the roof of each container shall be taken at 5 megapixels or more and kept online for at least 90 days. **IMPORTANT**

3.3 UHF RFID readers shall comply with ISO/IEC 18000-63 (EPC Gen2). The supplier shall deliver 3,000 tamper-evident windscreen tags. **MANDATORY**

3.4 For a pre-booked truck with no exception, the in-gate transaction, from arrival at the portal to the barrier opening, shall take no more than 60 seconds on average. **MANDATORY**

3.5 Kiosks shall offer an Arabic and English interface and an intercom to the gate control room, and print a gate pass showing the assigned yard position. **IMPORTANT**

3.6 The GOS shall provide lane control, an exception-handling workstation showing all images of the transaction, and dashboards of transactions per hour, average transaction time and exceptions by type. **IMPORTANT**

SAMPLE · FICTIONAL

3.7 Real-time integration with the T2 TOS (REST or UN/EDIFACT CODECO/COARRI), the PCS Vehicle Booking System (appointment check) and the customs release status provided through the PCS. A truck shall not be let in without a valid appointment, nor a container out without customs release. **MANDATORY**

3.8 All servers, storage and software shall be installed in the Authority's Terminal 2 server room, with a standby server in the Authority's main data centre. The system shall comply with the Authority's Port Operational Technology Standard (POTS-2026). **MANDATORY**

3.9 Availability of at least 99.5 % per calendar month. When the GOS is unavailable, the lanes shall switch to a manual mode operated from the kiosks and the control room. **MANDATORY**

3.10 Outdoor equipment shall be rated IP66 or better, for continuous operation from 0 °C to +55 °C in a saline coastal atmosphere. **MANDATORY**

4. Implementation

4.1 All 6 lanes shall be in operation within 8 months of contract signature. Lanes are cut over one pair at a time; at least 4 lanes shall stay open during the works. **MANDATORY**

4.2 Acceptance follows a Site Acceptance Test and a 30-day performance test in live operation, which measures OCR accuracy and transaction times against clauses 3.1 and 3.4. **MANDATORY**

4.3 Training of 20 gate clerks and control-room operators, and of 6 maintenance technicians of the Authority. **IMPORTANT**

5. Warranty and maintenance

5.1 Warranty of 24 months from acceptance, covering all equipment and software, parts and labour. **MANDATORY**

5.2 Maintenance for 3 years after the warranty, including preventive maintenance, software updates and repairs, priced per year. **MANDATORY**

5.3 On-site response within 4 hours, 24 hours a day and 7 days a week, to any fault that stops a lane, from a spare-parts stock held in the State. **IMPORTANT**

6. Commercial conditions

6.1 Prices in United States Dollars (USD), excluding VAT, fixed for the duration of the contract, including the maintenance years. **MANDATORY**

6.2 Payment schedule: 15 % advance against an advance-payment guarantee, 45 % on delivery of the equipment to site, 40 % on acceptance. Maintenance is invoiced yearly. **IMPORTANT**

6.3 Performance security of 10 % of the contract price, valid until 28 days after the end of the warranty. **MANDATORY**

6.4 Bid validity of 120 days. Bid security of USD 40,000, issued or confirmed by a bank licensed in the State. **MANDATORY**

SAMPLE — FICTIONAL

7. Evaluation

7.1 Bids are first checked against the mandatory requirements. Compliant bids are scored 70 % technical (solution 30, measured performance 20, implementation plan 20, maintenance and support 15, references 15) and 30 % commercial.

7.2 Evaluated price = supply and installation + 3 years of maintenance after the warranty.

7.3 Bidders shall complete the compliance matrix in Annex 1 and give the section of their technical proposal where each requirement is answered.

Chair, Tender Committee
Northern Gulf Ports Authority

Issued: 5 October 2026
Reference: NGPA/T/2026/031

SAMPLE · FICTIONAL

Annex 1. Compliance matrix (to be completed by the bidder)

For each clause, state Comply, Partially comply or Do not comply, and the section of the technical proposal where the requirement is answered.

Clause	Requirement	Response	Reference in the proposal
3.1	OCR accuracy: containers ≥ 98 %, plates (Arabic and Latin) ≥ 97 %, up to 15 km/h		
3.2	Damage images, 4 sides and roof, ≥ 5 MP, 90 days online		
3.3	UHF RFID ISO/IEC 18000-63, 3,000 tags		
3.4	Average in-gate transaction ≤ 60 s		
3.5	Kiosk: Arabic and English, intercom, gate pass		
3.6	GOS: lane control, exceptions, dashboards		
3.7	Integration: TOS, PCS Vehicle Booking System, customs release		
3.8	On-premise in T2 server room and main data centre; POTS-2026		
3.9	Availability ≥ 99.5 %; manual mode		
3.10	IP66, 0 °C to +55 °C		
4.1	All 6 lanes in operation within 8 months		
4.2	SAT and 30-day performance test		
4.3	Training: 20 operators, 6 technicians		
5.1	Warranty 24 months		
5.2	3 years of maintenance after warranty		
5.3	On-site within 4 h, 24/7; spare parts in the State		

SAMPLE — FICTIONAL