جدول الكميات — مناقصة صيانة مبنى مركز خدمات المتعاملين - تجريبية

S.No.	Description	Qty.	Unit	Unit Price	Amount
1	Demolition of existing wall tiles and disposal of debris off site.	220	sqm		
2	Removal of existing washroom fixtures (WC, wash basin, accessories).	6	item		
3	Demolition of existing false ceiling in the customer hall.	140	sqm		
4	Supply and fixing of 60x60 cm porcelain floor tiles with adhesive and grout.	310	sqm		
5	Supply and fixing of 1200x600 mm porcelain wall tiles in washrooms.	180	sqm		
6	Supply and application of cementitious waterproofing in wet areas.	95	sqm		
7	Supply and installation of moisture-resistant gypsum false ceiling.	140	sqm		
8	Two coats of emulsion paint on internal walls after one coat of primer.	860	sqm		
9	Supply and installation of solid wood doors 90x220 cm with ironmongery.	8	no		
10	Supply and installation of washroom vanity counters with quartz top.	4	no		
11	Supply and installation of wall-hung WC with concealed cistern.	6	no		
12	Supply and installation of LED panel lights 60x60 cm, 40 W.	48	no		
13	Replacement of split air-conditioning units 2 tons, including piping.	5	no		
14	Cleaning of air ducts and grilles of the ground and first floors.	1	LS		